


GOLD LATCH REPLACEMENT PROCEDURE S



RK-10632-1

For PH-10RP51, PH-30SA51, PH-30SB51 and PH-30RP51 Pintle Hooks With a Pin and Lanyard

VERIFY KIT CONTENTS




Kit Contains:


ITEM	PART NO.	QTY
Α	XA-10632-1	1
В	XB-T-89-4	1
С	XB-11157	1
D	XB-11048	2
E	Never-Seez®	1

Never-Seez® is a registered trademark of Bostik, Inc.


PRODUCT IDENTIFICATION




PH-10RP51 PINTLE HOOK For additional information, reference XL-PH370



PH-30SA51 PINTLE HOOK For additional information, reference XL-PH369




PH-30SB51 PINTLE HOOKS For additional information, reference XL-PH371



PH-30RP51 PINTLE HOOK For additional information, reference XL-PH364

PROCEDURE

 Grind off head of rivet and discard rivet, latch assembly and pin and lanyard.




2. Apply Never-Seez* to entire shaft of the new pivot bolt (not on thread).




3. Install the new latch assembly using the new pivot bolt and nut. Tighten nut until it contacts the cast latch and apply an additional 1/4 turn to the nut. Visually verify that a full thread protrudes beyond the nut. If it becomes necessary to remove the lock nut, discard and use the second nut provided in the kit.

MARNING DO NOT reinstall a removed lock nut. Always install a new lock nut when removing or replacing latch assembly. A reinstalled nut may not retain properly and could result in an unintended trailer separation.



4. Check the latch for proper operation. It should open and close freely. When closed, the lock handle (A) will rotate and move down until it is flush with the top of the latch.



The tertiary lock pin should fit without restriction through the holes in the latch (see illustrations above).



SAF-HOLLAND USA, Inc. 888.396.6501 Fax 800.356.3929

2

SAF-HOLLAND Canada Limited 519.537.3494 Fax 800.565.7753 Western Canada 604.574.7491 Fax 604.574.0244 **SAF-HOLLAND International, Inc.** 616.396.6501 Fax 616.356.1511

Copyright © November 2007-SAF-HOLLAND, Inc. All information contained in this document was correct at time of copyright, and is subject to change without notice. All rights reserved.